

3-23

API NUMBER: 15-159-20,728 . 0000

OPERATOR LICENSE # 5893
OPERATOR Pratt Well Service
NAME & P O Box 847
ADDRESS Pratt, KS 67124

660 ~~4620~~
1140

FEET FROM ~~S~~ SECTION LINE
FEET FROM ~~E~~ SECTION LINE

LEASE NAME: Dick Twin # ONE
COUNTY: Rice
WELL TOTAL DEPTH: 3334 108.30592
PIPE: 5 1/2" - 3259
SURFACE CASING: 8 5/8"-310

ABANDONED OIL WELL XX GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: Pratt Well Service
ADDRESS: Pratt, KS> 67124 LICENSE: 5893

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 23rd MONTH: March YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM: Frank Vogal
COMPANY NAME: Acid Service PHONE: 316-672-1201
WERE: Sand bottom 3170-5 sacks
1250'-35 sacks
750' - 35 sacks
360' - 0

RECEIVED
KANSAS CORPORATION CO.

RECEIVED
KANSAS CORPORATION COMMISSION

APR 07 1999

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi

CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { XX } PART { } NONE { }

COMPLETED: HOUR: 3:30 DAY: 23rd MONTH: March YEAR: 1999

ACTUAL PLUGGING REPORT: Sanded bottom to 3170' and 5 sacks of common, shot 5 1/2" casing off at 1310'. Pulled all of casing. Ran tubing into 1250'. Pumped 35 sacks. Pulled to 750'. Pumped 35 sacks. Pulled to 360' circulated cement to surface.

REMARKS: Acid Service # 00752 60/40 4%

INVOICED

DATE 4-2-99
INV. NO. 60774

PIRT

~~I DID OBSERVE THIS PLUGGING~~

JACK LUTHI

FORM CP-2/3
REV. 3/90