

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-21792-0000

NE, Sec. 24, T ²⁰~~20~~ S, R 9 W

2310 feet from N section line

990 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5079

Lease Name Habiger Well # 1

Operator: Edwards Oil, Inc.
Name & Address P.O. Box 206
Hutchinson, Kansas 67501

County Rice

Well Total Depth 3493 feet 113.52

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 204

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address Box 823, Great Bend, Kansas 67530

Company to plug at: Hour: 3:00 P Day: 25 Month: February Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Leonard Williamson

(company name) Duke Drilling Co., Inc. (phone) 316 792 1171

were: Fill hole with heavy mud. Pump 50 sacks 50/50 Perm mix w/ 2% gel and 3% c.c. through drill pipe at 260'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks Perm mix. Cement rat hole with 10 sacks Perm mix.

Signed [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 PM Day: 25 Month: February Year: 1984

ACTUAL PLUGGING REPORT Hole Filled with heavy mud. 50 sacks 50/50 Perm mix pumped through drill pipe at 260'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement.

Remarks: Halliburton Co. Ticket # 778724

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

Signed [Signature] (TECHNICIAN) ✓

INVOICED
DATE 3-6-84
INV. NO. 0534

RECEIVED
STATE CORPORATION COMMISSION
MAR 02 1984
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 9-82
MLU