

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barton

County. Sec. 30 Twp. 20 Rge. 13 (E) (W)

Location as "NE/CNW&SW" or footage from lines NE SE NE
Lease Owner A. E. Branine
Lease Name Murphy Well No. 1
Office Address 1609 Hillcrest, Newton, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 23, 1956 19
Application for plugging filed February 23, 1956 19
Application for plugging approved February 23, 1956 19
Plugging commenced February 23, 1956 19
Plugging completed February 23, 1956 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3625 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Pipe	0	140'	8-5/8"	140'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 160'.
Bridged hole at 160'. Ran 30 sacks
cement 160' up. Bridge hole at 40',
ran 10 sacks cement. Plug 40' to
base of cellar.

Name of Plugging Contractor Isern Drilling Company (If additional description is necessary, use BACK of this sheet)
Address Box 45, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON
I. M. M. Shropshire (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. M. M. Shropshire
Lyons, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of February, 1956

My commission expires Feb. 10, 1959.

George A. Meyer
Notary Public.

PLUGGING
FILE SEC 30 T 20 R 13W
BOOK PAGE 41 LINE 17

RECORDED
CONSERVATION DIVISION
Wichita, Kansas
3-1-1956

WELL LOG

A. E. BRANINE et al, Owner - Murphy #1
 NE/4 SE/4 NE/4 Section 30, Township 20, Range 13W,
 Barton County, Kansas

ELEVATION: 1893 DF

Figures indicate bottom of formation
 0 to

130 sand
 150 sand stone
 340 shale & shells
 350 shale
 400 sand & shale
 749 shale
 775 Anhydrite
 1280 shale & shells
 1500 salt
 1625 shale & shells
 2240 lime & shale
 2270 shale & shells
 2425 lime & shale
 2730 shale & shells
 3109 lime & shale
 3112 Heebner
 3401 lime & shale
 3445 lime
 3515 lime & shale
 3557 lime, chert & shale
 3612 Arbuckle
 3622 lime
 3625 Granite
 3625 Rotary
 Total Depth D&A

PIPE RECORD:

8-5/8" set at 140'
 Cemented with 235 sacks

Rotary Commenced 2- 9-56
 Completed 2-23-56

STATE OF KANSAS)
 COUNTY OF BARTON) SS

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 27th day of February, 1956.

STATE OF KANSAS)
 COUNTY OF BARTON)
 MAR 1 - 1956
 CONSERVATION DIVISION
 Wichita, Kansas

George D. Meyer
 Notary Public

My commission expires Feb. 10, 1959.

PLUGGING
 NE/4 SE/4 T. 20, R. 13W
 BOOK PAGE 41 LINE 17