

STATE CORPORATION COMMISSION  
200 Colorado Bldg Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-0009-22,519

15.009.22519.0000

LEASE NAME Christiansen

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1 A

990 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 13 TWP. 20S RGE. 13 (E) or (W)

COUNTY Barton

Date Well Completed N/A

Plugging Commenced 07-22-96

Plugging Completed 07-24-96

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 100 N. Main, Suite 1000, Wichita, Kansas 67202

PHONE (316) 262-3596 OPERATORS LICENSE NO. 9408

Character of Well oil

(oil, gas, O&A, SWD, Input, Water supply Well)

The plugging proposal was approved on 07-22-96

(date)

by Herb Deines

(KCC District Agent's Name)

Is Acc-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation N/A Depth to top 3467' Bottom 3469' r.c. 3517'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface			8 5/8"	213'	0
	Production			4 1/2"	3517'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from feet to feet each set. Bottom plug, sanded off to 3400' 4 sks of cement. Allied mixed 35 sks at 1522'. Displaced it down to 700'. Circulated cement to surface from 700' with 300 lbs. of hulls mixed in 135 sks of cement. Topped off with 30 sks of cement.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc.

License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

RECEIVED  
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Trans Pacific Oil Corporation

AUG 12 1996

STATE OF Kansas

COUNTY OF Barton, ss.

Joseph F. Strube

(Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Joseph F. Strube


(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 96

Karlynn K. Beck  
Notary Public

My Commission Expires: 09-28-98

USE ONLY ONE SIDE OF EACH FORM



Form CP-4  
Revised 05-88

15.009-22516-0000

# Electra Log

Inc.

Sheet 13 of 20S and 13W  
*Radiation Guard*  
*Log*

	COMPANY TEXAS ENERGIES, INC.	
	15-009-22516	
	WELL CHRISTIANSEN "A" #1	
	FIELD BEND	
COUNTY BARTON	STATE KANSAS	
Location C S/2 OF NW NW	Other Services	
Sec 13 Twp. 20S Rge 13W		

Permanent Datum: GROUND LEVEL Elev. 1851'	Elev. K.B. 1860'
Log Measured From K.B. NINE 11. Above Perm. Datum	D.P. 1857'
Drilling Measured From KELLY BUSHING	G.I. 1851'

Date	4-6-82			
Run No.	ONE			
Depth - Driller	3517'			
Depth - Logger	3516'			
Bot. Log Inter.	3515'			
Top Log Inter.	0			
Casing - Driller	8 5/8" 213'			
Casing - Logger				
Bit Size	7 7/8			
Type Fluid in Hole	PREMIX STARCH MUD			
Dens.   Visc.	9.3   46			
pH   Fluid Loss	6.4   12.0 ml			
Source of Sample	FLOLINE			
Rm @ Meas. Temp.	.21 .58			
Rm @ Meas. Temp.	.16 .58			
Rm @ Meas. Temp.	.32 .58			
Source: Re- Re-	CHARTS			
Rm @ BHT	.10 @ 112			
Time Since C. c.	4 HOURS			
Max. Rec. Temp.	112			
Equip.   Location	137   GREAT BEND			
Recorded By	V. BRUNO			
Witnessed By	MR. RON FALWELL			

CHRISTIANSEN  
 15-009-22516-0000  
 4-6-82  
 11:11 AM