


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 13 Twp. 20S Rge. (E) 13W(W)

Location as "NE/CNWxSWx" or footage from lines SE NW SW

Lease Owner Circle Oil Company, Inc.

Lease Name SELLE Well No. 1

Office Address 500 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 29, 19 66

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced September 29, 19 66

Plugging completed September 29, 19 66

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Don Truan)

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3520 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	204'	8-5/8"	9/22/66	----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 200 Feet; Hulls and Plug with 25 sacks cement thru the drill pipe; Mud to 40 feet; 1/2 sack Hulls and Plug and cement to base of cellar; 2 sacks in rat hole. Job completed at 1:30 A.M.

10-06-1966
RECEIVED
STATE CORPORATION COMMISSION

OCT 6 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co.
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Thomas M. McCaul, Jr. (employee of owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
500 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of October, 1966

My commission expires November 26, 1966. Louise K. Whitted - Notary Public.

DRILLERS LOGSELLE NO. 1

CASING RECORD: 8-5/8" @ 204'
w/175 sax cement

TOTAL DEPTH:
3520'

COMPANY: Circle Oil Co., Inc.

CONTRACTOR: Sage Drilling Co.

COMMENCED: September 22, 1966

COMPLETED: September 29, 1966

DESCRIPTION: SE NW SW
Sec. 13-20S-13W
Barton County, Kansas

ELEVATION: 1859KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	160	
Hard Sand & Pyrite	160	165	
Shale	165	675	
Anhydrite	675	705	
Shale & Shells	705	1555	
Sandy Lime & Shale	1555	1785	
Lime & Shale	1785	2440	
Shale & Lime	2440	2773	
Lime & Shale	2773	2905	
Lime	2905	3000	
Lime & Shale	3000	3256	
Lime	3256	3310	
Lime & Shale	3310	3365	
Lime	3365	3405	
Lime & Shale	3405	3520	

RECEIVED
STATE CORPORATION COMMISSION

OCT 6 1966

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By

Thomas M. McCaul, Jr.
Thomas M. McCaul, Jr.

Subscribed and sworn to before me this 5th day of October, 1966.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1966.