


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barton County, Sec. 13 Twp. 20 Rge. 13 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines. NW NE NW
Lease Owner Leo J. Dreiling Oil Co.
Lease Name Christiansen Well No. #2
Office Address R. R. #2 Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed August 20 1969
Application for plugging approved August 25 1969
Plugging commenced August 30 1969
Plugging completed September 6 1969
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	221	None
				4 1/2	3413	2318

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

August 30 Dumped sand to 3150', Mixed and dumped 4 sx of cement to 3100' to plug off bottom
September 6 Mixed and pumped 20 sx of gel down 8 5/8 casing. Released plug and mixed and pumped 90 sx of Portland Cement down 8 5/8 casing


RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Russ Casing Pulling, Inc.
Address P. O. Box 1082 Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

Subscribed and sworn to before me this 15th day of September, 1969
Joseph A. Hess
JOSEPH A. HESS Notary Public.



L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Company
Route 2
Victoria, Kansas 67671
Farm Christiansen No. 2
Total Depth 3470'
Comm. 3-16-68 Comp. 3-22-68
Contractor L. J. Dreiling & Sons, Inc.
Route 2
Victoria, Kansas 67671

Sec. 13 Twp. 20 Rng. 13
Location 100' S NW-NE-NW/4
County Barton
Elevation: 1855' K.B.
1852' D.F.
1850' G.R.

Casing Record Cement Record
221' - 8 5/8" 200 sacks cement
3413' - 4 1/2" 125 sacks cement

Production:

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1969
CONSERVATION DIVISION
Wichita, Kansas

Figures Indicate Bottom of Formations

0'	40'	Top Soil & Sand
40'	200'	Sand
200'	221'	Gravel & Shale
221'	668'	Shale & Redbed
668'	695'	Anhy.
695'	1445'	Shale
1445'	1525'	Shale
1525'	1810'	Shale & Lime
1810'	2110'	Shale & Lime
2110'	2186'	Shale & Lime
2186'	2500'	Shale & Lime
2500'	2740'	Shale & Lime
2740'	2930'	Shale & Lime
2930'	3035'	Lime
3035'	3220'	Lime
3220'	3235'	Lime
3235'	3270'	Lime
3270'	3335'	Lime
3335'	3370'	Lime
3370'	3450'	Lime
3450'	3470'	Lime
3470'	T.D.	

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo J. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoins is a true and correct copy from the Daily Drilling Report from your Christiansen #2.

Leo J. Dreiling
Leo J. Dreiling

Subscribed and sworn to before me this 25th day of March 1968.

Joseph A. Hess
Joseph A. Hess Notary Public

