


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 13 Twp. 20 Rge. 13 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Leo J. Dreiling Oil Company
Lease Name Christiansen Well No# 1
Office Address R. R. #2 Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed August 20 1969
Application for plugging approved August 25 1969
Plugging commenced August 28 1969
Plugging completed September 6 1969
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	197	None
				5 1/2	3510	2590

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

August 28, 1969 Dumped sand to 3225', mixed and dumped 5 sx of cement to 3185'.

September 6, 1969 Pumped 20 sx of gel down 8 5/8 casing. Released 8 5/8 plug and mixed and pumped 90 sx of Portland Cement down 8 5/8 casing.


RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1969
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Russ Casing Pulling, Inc.
Address P. O. Box 1082 Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF ELLIS, ss.
I, Leo F. Dreiling

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)



Subscribed and sworn to before me this 15th day of September, 1969
September 19, 1970
My Commission Expires _____

Joseph A. Hess
JOSEPH A. HESS Notary Public.

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Company
Victoria, Kansas

Sec. 13 Twp. 20 Rng. 13

Farm Christiansen No. 1

Location NW-NW-NW

Total Depth 3510'

County RUSSELL COUNTY, KANSAS

Comm. 8-20-61 Comp. 8-28-61

Elevation: D.F. 1855'

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas

G.R. 1853'

Casing Record	Cement Record	Production:
197' - - - - 8 5/8"	240 sags cement	Arbuckle
3508' - - - - 5 1/2"	150 " "	" "

Figures Indicate Bottom of Formations

0 - 65	Surface clay & sand
65 - 120	Sand
120 - 145	Iron
145 - 197	Shale
197 - 295	Shale
295 - 666	Redrock
666 - 694	Anhydrite
694 - 840	Shale & Shells
840 - 1368	Shale & Shells
1368 - 1604	Shale & Lime
1604 - 1765	Shale & Lime
1765 - 1867	Lime
1867 - 1997	Lime
1997 - 2180	Lime & Shale
2180 - 2320	Shale & Lime
2320 - 2534	Shale & Lime
2534 - 2655	Lime & Shale
2655 - 2810	Shale & Lime
2810 - 2819	Lime & Shale
2919 - 2967	Lime
2967 - 3036	Lime
3036 - 3101	Lime
3101 - 3242	Lime
3242 - 3256	Lime
3256 - 3275	Lime
3275 - 3345	Lime
3345 - 3422	Lime
3422 - 3467	Lime & Arbuckle
3467 - 3510	Arbuckle
3510	TD

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1969
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy of the log from the Daily Drilling Report on your Christansen #1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 16th day of September, 1961.

Samuel Zimmerman
NOTARY PUBLIC

My Commission Expires: 8-14-65