

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 8 TWP. 20s RGE. 13w E/W
Location as in quarters or footage from lines:
NE SW NW

Locate Well
correctly on above
Section Platt.

Lease Owner Raymond Oil Co., Inc.
Lease Name Nicolet #1 Well No. _____
Office Address One Main Place, Suite 900, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 12/10/82
Plugging completed 12/15/82

Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation _____ Depth to top _____ bottom _____ T.D. 3565'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	763'	none
				5 1/2"	3564'	2215'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged bottom with 5 sacks cement, sand to 3150' & 5 sacks cement.
Shot pipe at 2421' 2323' & 2233'. Layed down 60 joints. Plugged well
with 25 sacks cement, 4 hulls, 12 gel, 50 cement, 3 gel, 1 hull, plug,
and 90 cement.

Plugging complete


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 1982



My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION
Irene Hovner
Notary Public.
DEC 22 1982

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: July 10, 1980
 DATE COMPLETED: July 18, 1980

Raymond Oil Co., Inc.
 Nicholet #1
 NE SW NW
 Sec. 8, T20S, R13W
 Barton County, Ks.

0 - 150'	Sand
150 - 554'	Clay, Shale, Red Bed
754 - 774'	Anhydrite
774 - 2882'	Shale, Shells, Lime
2882 - 3092'	Lime
3092 - 3096'	Shale
3096 - 3113'	Lime & Shale
3113 - 3128'	Lime
3128 - 3201'	Shale
3201 - 3214'	Lime & Shale
3214 - 3422'	Lime
3422 - 3476'	Lime, Shale, Congl.
3476 - 3565'	Dolomite
3565'	RTD

ELEVATION: 1870 K.B.

FORMATION DATA

Anhydrite	754'
Topeka	2882'
Heebner	3092'
Toronto	3118'
Douglas	3128'
Br. Lime	3201'
Lansing- K.C.	3214'
Base K. C.	3422'
Conglomerate	3434'
Arbuckle	3476'
RTD	3565'

Surface Pipe: Set new 20#, 8-5/8" pipe at 763' w/450 sacks 50/50 pozmix, 2% gel, 3% cc.

Production Pipe: Set new 5 1/2", 11# & 15# casing at 3564' w/120 sacks 60/40 pozmix, & 40 sacks 60/40 pozmix w/35 gal. Latex.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 22nd day of July 1980.

My Comm. Expires:

4-11-1982

Lois M. Hague
 Notary Public