

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barton County. Sec. 7 Twp. 20 Rge. 13 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$ SW $\frac{1}{2}$ SW $\frac{1}{4}$ 990' from S330' fw
Lease Owner Grant Oil Co.

Lease Name Taylor Well No. 1

Office Address 814 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed June 14 19 52

Application for plugging filed June 14 19 "

Application for plugging approved June 14 19 "

Plugging commenced June 14 19 "

Plugging completed June 14 19 "

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Never Produced 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Strough

Producing formation Arbuckle Depth to top 3509' Bottom 3576' Total Depth of Well 3576' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Dakota Water	Salt water	560'	575'			
and surface water	Fresh water	20'	110'	8 5/8 "	800'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set a Halliburton plug at 270' with 20 sacks of cement.
Filled with mud to within 35' of the surface. Set another plug and 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL - 1 1952 7-01-1952

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Grant Oil Co.
Address 814 Central Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

I, Paul Pfeifer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Pfeifer

SUBSCRIBED AND SWORN to before me this 27th day of June, 1952

My commission expires 9-4-54

(Address) Roy Gillis
Notary Public.

PLUGGING
FILE SEC-T-R

TAYLOR NO. 1

NW/4 SW/4 SW/4 of Sec. 7-20S-13W,

Barton County, Kansas

Rigging up Rotary Tools 6-2-52 Run 800' of 8 5/8" surface pipe.
 Tearing down 6-14-52 Set at 790' cemented w/425 sx
 cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale	0	350
Red Bed	350	450
Sand & Red Bed	450	510
Red Bed	510	695
Shale & Red Bed	695	725
Shale	725	735
Sahle	735	785
Lime	785	790
Anhydrite	790	815
Red Bed	815	890
Sahle & Shells	890	1530
Shale with Shells	1530	1656
Lime	1656	2070
Shale with lime streaks	2070	2180
Shale with lime streaks	2180	2310
Lime & shale	2310	2585
Lime with shale breaks	2585	2880
Lime	2880	3205
Shale	3205	3240
Lime	3240	3576 T.D.

I, Wm. F. Rothrock, hereby certify that the above log is true and correct, to the best of my knowledge and belief.

W. F. Rothrock

Subscribed and sworn to before me this 23rd day of June, 1952.

Alice M. Oaks
 Notary Public

My commission expires: August 17, 1955.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL - 1 1952
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FBI SEC-7720134
 BOOK PAGE 26 LINE 6