


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 14 Twp. 20 Rge. 13 (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines NE NE NE
Lease Owner Leo J. Dreiling Oil Company
Lease Name Moore Well No. 1
Office Address Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 3-29-61 19__
Application for plugging filed 3-29-61 19__
Application for plugging approved 3-29-61 19__
Plugging commenced 3-29-61 19__
Plugging completed 3-29-61 19__
Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ?
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3515' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|--------------|---------|------|----|--------|--------|------------|
| Surface Pipe | | | | 8 5/8" | 195' | -0- |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rotary mud was used in filling up hole to a depth of 190' where a plug was set using 1/3 sacks hulls and 25 sacks cement then filling hole with rotary mud to a depth of 35' using 1/3 sacks hulls and 10 sacks cement and filling hole to top.

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1962

CONSERVATION DIVISION
Wichita, Kansas

8-23-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. DREILING & SONS, INC.
Address VICTORIA, KANSAS

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling a partner (employee, owner, or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 62

My commission expires August 14, 1965

Notary Public.

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Company
Victoria, Kansas

Sec. 14 Twp. 20 Rng. 13

Farm Moore No. 1

Location NE NE NE

Total Depth 3515'

County Barton County

Comm. March 21, 1961

Comp. March 29, 1961

Elevation: D. F. 1858'

Contractor L. J. DREILING & SONS, INC.
VICTORIA, KANSAS

G. R. 1855'

Casing Record

Cement Record

Production

8 5/8" - - - - 195'

200 sacks cement

D & A

Figures Indicate Bottom of Formations

0 - 50
50 - 135
135 - 195
195 - 230
230 - 280
280 - 680
680 - 710
710 - 890
890 - 1535
1535 - 1605
1605 - 1735
1735 - 1815
1815 - 2120
2120 - 2420
2420 - 2640
2640 - 2805
2805 - 2887
2887 - 2979
2979 - 3030
3030 - 3114
3114 - 3230
3230 - 3264
3264 - 3316
3316 - 3380
3380 - 3489
3489 - 3515
3515

Surface Clay
Iron
Shale
Shale & Shells
Shale
Red Bed
Anhydrite
Red Bed
Shale & Shells
Shale & Lime
Lime
Lime
Lime & Shale
Shale & Lime
Shale
Shale & Lime
Shale & Lime
Lime
Lime
Lime
Lime
Shale & Lime
Lime
Lime
Lime
Lime
Lime
TD

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1962

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF ELLIS) ss.

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report on your Moore No. 1.

Leo F. Dreiling
Leo F. Dreiling

Subscribed and sworn to before me this 17th day of August, 1962.

Ramon Zimmerman
NOTARY PUBLIC

My Commission Expires: August 14, 1965