

API NUMBER 15.609.23170.0000

LEASE NAME Panning #1

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #1

2310 Ft. from S Section Line

380 Ft. from ~~W~~ Section Line

SEC. 12 TWP. 20 RGE. 13W (E) or (W)

COUNTY Barton

LEASE OPERATOR RIVERSIDE PETROLEUM COMPANY

ADDRESS 314 East Santa Fe, Ellinwood, Ks. 67526

PHONE# (316) 564-2575 OPERATORS LICENSE NO. 04540

Date Well Completed 11-83

Character of Well Oil

Plugging Commenced March 2, 1987

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed Sept. 9, 1987

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District # 6 Hays, Ks. 67601

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle & K. C. Depth to Top 3164 Bottom 3148 T.D. 3508

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				5"	3508	1887
				8/5/8	257	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sanded back hole to 3147, then added 1 sack quick set cement, sanded K. C. formation back to 3211, dumped dump trailer 5 sacks portland cement. Pumped in 125 sks. ATL 250# of Hulls, and 3sks. of Gel., went on vacuum, mixed 35 sks. of 60/10 with 6% Gel. and 300# of hulls, Pumped in & no shut in pressure. 2 days hole 79ft. added 1 yard Ready mix.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor UNITED CEMENTING CO. & Hembree Well Ser. License No. 06907

Address P. O. BOX 31 Russell, Ks. 67665

STATE OF KANSAS COUNTY OF ~~KANSAS~~ Barton, ss.

Lloyd Bryant

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Lloyd W Bryant

(Address) 314 E. Santa Fe, Ellinwood, KS 67526

SUBSCRIBED AND SWORN TO before me this 10th day of Sept., 19 87

Cheri Balun  
 Notary Public

My Commission Expires: July 9, 1988

SEP 11 1987 9-11-1987

