

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 12 TWP. 20s RGE. 13 E/W
Location as in quarters or footage from lines:
100' W of SE SW SW

		12	

Lease Owner Texas Energies, Inc.
Lease Name Parrish Well No. 1-A
Office Address Box 947 Pratt, KS 67124
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 3-27-82
Application for plugging filed 3-31-82
Plugging commenced 3-27-82
Plugging completed 3-27-82
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bud Metz

Producing formation -- Depth to top -- bottom -- T.D. 3535

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
None				8 5/8	212.53	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from feet
to feet for each plug set.

Plugged well with 123 sxs 50-50 poz mix 3% CC 2% Gel as follows:
cement plug at 600' with 60 sxs
cement plug at 240' with 40 sxs
solid bridge plug at 40' with 1/2 sx hulls and 10 sxs
rathole with 10 sxs
water well with 3 sxs

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Texplor Drilling

STATE OF Kansas COUNTY OF Pratt, ss.
E. H. Bittner (employee of owner) or ~~(owner or operator)~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.


(Signature) Edwin H. Bittner
Box 947 Pratt, KS 67124
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 82

My Commission expires: April 23, 1983



Notary Public.



TEXAS ENERGIES, INC.

DRILLER'S WELL LOG

Parrish 1-A
100' W of SE SW SW, Sec. 12-20s-13w
Barton County, Kansas

Commenced: 3-19-82

Completed: 3-26-82

OPERATOR: Texas Energies, Inc.

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
<u>FROM</u>	<u>TO</u>		
0	212	Sand & Shale	Spudded 3-19-82.
212	1360	Shale-Lime	Ran 5 jts. 8 5/8" 32# 8 rd. used casing with 50 sxs Lite 3% CC and 50 sxs Common 2% Gel 3% CC set at 212.53', T.D. 220'. Job complete at 5:00 p.m. 10-20-81.
1360	2350	Lime-Shale	
2350	3095	Lime-Shale	
3095	3252	Lime-Shale	
3252	3278	Lime-Shale	
3278	3400	Lime-Shale	
3400	3462	Lime-Shale	
3462	3535	Arbuckle	Total depth of well 3535'. Plugged well with 123 sxs 50-50 poz mix 3% CC 2% Gel: cement plug at 600' with 60 sxs; cement plug at 240' with 40 sxs; solid bridge at 40' with 1/2 sx hulls and 10 sxs; rathole with 10 sxs; water well with 3 sxs. Plug down at 2:00 p.m. 3-27-82.

STATE OF KANSAS)

) ss.

COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

TEXAS ENERGIES EXPLORATION CO., INC.

My commission Expires:

April 23, 1983

