


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Barton County. Sec. 11 Twp. 20 Rge. 13 (E) W (W)  
Location as "NE/CNW/SE" or footage from lines SW SW SW  
Lease Owner Leo J. Dreiling Oil Co.  
Lease Name Parrish Well No. 1  
Office Address RR#2 Victoria, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed Feb. 8, 1969  
Application for plugging approved Feb. 11, 1969  
Plugging commenced Feb. 7, 1969  
Plugging completed Feb. 11, 1969  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production February 1969  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	190'	None
				5 1/2	3449'	2544'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 3258' to 3180'. Mixed and dumped 5 sx. of cement from 3180' to 3140'. Pulled casing. Mixed and pumped in 20 sx. of gel mud ####. Mixed and pumped in 90 sx. of cement from 270' to base of the cellar.



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Russ Casing Pulling Inc.  
Address Box 1082 Great Bend, Ks.

STATE OF KANSAS COUNTY OF ELLIS, ss.  
I, Leo F. Dreiling (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671  
(Address)



to before me this 3rd. day of March, 19 69  
Joseph A. Hess  
Notary Public.

15.009.15914.0000

L. J. DREILING and SONS, Inc.  
VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Company  
Victoria, Kansas

Sec. 12 Twp. 20 Rng. 13

Farm Parrish No. 1

Location SW SW SW

Total Depth 3490'

County Barton County, Kansas

Comm. August 11, 1961 Comp. August 19, 1961

Elevation: D. F.

Contractor L. J. Dreiling & Sons, Inc.  
Victoria, Kansas

G. R.

Casing Record

Cement Record

Production:

8 5/8" - - - - 190'

200 Sags Cement

Kansas City

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 11 1965  
CONSERVATION DIVISION  
Wichita, Kansas

Figures Indicate Bottom of Formations

0 - 50	Surface Clay
50 - 114	Surface Clay & Sand
114 - 123	Iron
123 - 157	Iron
157 - 190	Shale & Shells
190 - 300	Shale & Shells
300 - 570	Red Rock
570 - 668	Red Rock & Shale
668 - 692	Anhydrite
692 - 1157	Shale & Shells
1157 - 1525	Shale
1525 - 1690	Shale & Lime
1690 - 1850	Lime & Shale
1850 - 1965	Lime
1965 - 2180	Lime & Shale
2180 - 2519	Shale & Broken Lime
2519 - 2700	Shale & Lime
2700 - 2813	Lime & Shale
2813 - 2937	Lime & Shale
2937 - 3028	Lime
3028 - 3094	Lime
3094 - 3256	Lime
3256 - 3258	Lime
3258 - 3275	Lime
3275 - 3346	Lime
3346 - 3452	Lime
3452 - 3490	Lime
3490	TD

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF ELLIS )

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy of the log from the Daily Drilling Report on your Parrish #1.

Leo F. Dreiling  
LEO F. DREILING

Subscribed and sworn to before me this 22nd day of August, 1961.

Ronald C. Zimmerman  
NOTARY PUBLIC

My Commission Expires: 8-15-65