

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

15.009.23503.0000  
WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-23,503

LEASE NAME Parish

WELL NUMBER "B" #1

SPOT LOCATION W/2-SW-SW

SEC 12 TWP 20 RGE. 13(E) or (W)

COUNTY Barton

Date Well Completed \_\_\_\_\_

Plugging Commenced 9-5-85

Plugging Completed 9-16-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Blackbird Oil Co.

ADDRESS Box 1584, Great Bend, Kansas 67530

PHONE # (316) 792-2879 OPERATORS LICENSE NO. 6670

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3675'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	300'	None
				5-1/2"	3639'	2,389.42'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3,220' and 5 sacks cement. Shot casing at 2400'. Pulled 57 joint of 5-1/2" casing. Squeezed well with 4 sacks hulls, 25 sacks cement, 12 sacks gel, 40 sacks cement, 3 sacks gel, 1 sack hulls, released plug and pumped 105 sacks of 60/40 pozmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 800 psi and shut in 500 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111  
Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.  
(Signature) James W. Rockhold  
(Address) Box 698, Gt. Bend, Ks. 67530

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 17 1985  
CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 16th day of September, 1985

IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-87

My Commission expires: \_\_\_\_\_

Iona M. Leatherman  
Notary Public