

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR GRADY BOLDING CORPORATION

ADDRESS P. O. Box 486 Ellinwood, Kansas 67526

PHONE# (316) 564-2240 OPERATORS LICENSE NO. 7383

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 13, 1993 (date)

by Ken Kuhn (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3510'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	287	8 5/8"	287	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

25 sx. @ 3440', 20 sx. @ 665', circulate 90 sx. from 330' to surface, 15 sx. in rathole  
Total: 150 sx. 60/40 Pozmix, 6% Gel, 1/4# flo/seal per sack

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GRADY BOLDING CORPORATION

STATE OF KANSAS COUNTY OF BARTON, ss.

L. D. Davis (Employee of Operator) or (~~Operator~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well was prepared and filed that the same are true and correct, so help me God.


(Signature) L. D. Davis JUL 21 1993  
L. D. Davis

(Address) R.R. 1 Box 183 B Great Bend, KS

SUBSCRIBED AND SWORN TO before me this 20th day of July 1993

Bessie M. DeWerff  
Notary Public  
Bessie M. DeWerff

My Commission Expires: 5-20-97



DRILLER'S WELL LOG

DATE COMMENCED: 7-07-93

DATE COMPLETED: 7-14-93

0 - 785 Sand & Shale  
 785 - 1445 Shale  
 1445 - 1845 Sand, shale & Lime  
 2135 - 2365 Lime  
 2365 - 2805 Shale & Lime  
 2805 - 2965 Lime & Shale  
 2965 - 3510 Lime  
 3510 RTD

GRADY BOLDING CORPORATION

PARISH #1

E/2 SE SW Sec. 12-T20S-R13W

BARTON COUNTY, KANSAS

ELEVATION: 1845' GR 1850' KBSURFACE CASING:

8 5/8" set @ 287' W/180 sx. 60/40  
 Pozmix, 2% Gel, 3% CC

A F F I D A V I T


STATE OF KANSAS )  
 COUNTY OF BARTON ) ss

L. D. DAVIS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.



\_\_\_\_\_  
 L. D. Davis

Subscribed and sworn to before me this 20th day of July 1993.

Notary Public: Bessie M. DeWerff

My Commission expires: 5-20-97

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 21 1993

CONSERVATION DIVISION  
 Wichita, Kansas