

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 101-27

LOCATION 21W-21W-SW

SEC. 2 TWP. 20 RGE. 16-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Fleske

Operator Sunray Oil Corp. Address Box 4195 - G. Bend - Kans.

Field _____ County Rawl

Total Depth 3735 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8" - 1025 ft. Circulated with cement.
5/8 casing set at 3735 ft. 100 sacks of cement. Plugged
back to 3720 with cement & shot. Mixed 5 sacks of
cement at 3720 ft. Shot off & pulled the 5/8 casing - mud
to 250 ft. Set Rock Bridge & 15 sacks of cement at 250 ft.
Mud to 75 ft. Bridge & 10 sacks of cement
at the surface.

The West Supply Co. - Plugging Contractors

PLUGGING RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1951
CONSERVATION DIVISION
Wichita, Kansas

C. L. Stough
District Conservation Agent

9-9-51