

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 101-88

LOCATION NW-NE-SW

SEC. 7 TWP. 20S RGE. 16W

Dry Hole        Abandoned Oil Well X Abandoned Gas Well       

I have today completed supervision of plugging of:

Well No. 1 Lease Flaske

Operator Sunray Oil Co. Inc. Address Box #195 - A. Paul - Kans.

Field        County Parmer

Total Depth 3765 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 1027 ft. Circulated with cement.  
5 1/2 casing set at 3765 ft - 100 sacks of cement - Plugged  
back to 3720 ft. with cement & shot - Dumped 5 sacks  
of cement at 3720 ft - Shot off & pulled the 5 1/2 casing -  
Used to 250 ft - Set Rock Bridge & 15 sacks of cement  
at 250 ft - Used to 35 ft - Bridge & 10 sacks of  
cement at the surface.

The West Supply Co. - Plugging Contractor

STATE CORPORATION COMMISSION

SEP 24 1951

CONSERVATION DIVISION  
Wichita, Kansas

District Conservation Agent

Date 9 - 21 - 51

**PLUGGING**  
FILE SEC-2700-16W  
BOOK PAGE 101 OF 88