



15.159.06589.0000

GEORGE DOCKING	Governor
MARION BEATTY ¹	Chairman
HARRY G. WILES	-Commissioner
RICHARD C. BYRD	Commissioner
RAYMOND B. HARVEY	Secretary
CLYDE E. MILLIGAN	Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS
JEWEL M. OGDEN, Director

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1959

CONSERVATION DIVISION
Wichita, Kansas

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date November 28, 1959, authorized the following
plugging operation:

Operator's Full Name: Dallas Uranium and Oil Corporation

Complete Address: 511 Elm St., Dallas, Texas

Lease Name: McGlynn Well No. 1

Location: SW SW NW Sec. 21 Twp. 20 Rge. 9 (E) (W) X

County: Rice Total Depth: 3350

Oil Well	Gas Well	Input Well	SWD Well	D & A	X
----------	----------	------------	----------	-------	---

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole with heavy mud to 155'--push plug and $\frac{1}{4}$ sack hulls to 155' and cement with 20 sacks thru drill pipe. Fill hole to 40' with heavy mud--push plug and $\frac{1}{4}$ sack hulls to 40' and cement with 10 sacks. Bridge and cement rathole with 2 sacks.

Very truly yours,

Signed:

Signed: Wilbert L. Leonard
Conservation Division Agent