



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Lee Roy Legleiter of Sitrin Petroleum Corp. has this  
date requested permission to plug the following described well:

Mr. Sitrin Petro. Corp. guarantees payment of the plugging fee.

Operator's full Name: Sitrin Petroleum Corporation

Complete Address: Box 693, Great Bend, Kansas 67530

Lease Name: Batchman Well No. # 1

Location: SE NW NW Sec. 24 Twp. 20 Rge. 13 (E)(W) W

County: Barton Total Depth 3465 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Mike Wassinger was instructed to plug the well as follows:

8 5/8" csg. 198' Gwc. Perf. 3245'.

Sanded hole back to 3220' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 2 sax hulls, 20 sax mud, plug, &

100 sax cement with Allied Cementing Company's pump truck, cementing

from 340' to base of cellar.

Very truly yours,

Don L. ...  
Conservation Division Agent