



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1973
CONSERVATION DIVISION
Wichita, Kansas
2-2-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Orville Monroe of Clinton Oil Company has this
date requested permission to plug the following described well:

Mr. Clinton Oil Company guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 217 N. Water, Wichita, Kansas 67202

Lease Name: Habiger Well No. # 1

Location: SW SW SE Sec. 19 Twp. 20 Rge. 14 (E)(W) X

County: Barton Total Depth 3670 Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Dale Speers was instructed to plug the well as follows:

8 5/8" csg. 862' Cwc. Perf. 3299'. Well making water.

Displaced 3 sax hulls, 25 sax cement, & plug to 3000' with pump truck.

Squeezed well with 3 sax hulls, 20 sax mud, plug, & 100 sax cement

with Sun Cementing Company's pump truck, cementing from 350' to base

of cellar.

Very truly yours,

Dale Speers
Conservation Division Agent