

WELL PLUGGING RECORD
 K.A.R.-82-
 AUG 07 1996
 NOTICE: Fill out completely
 and return to Cons. Div
 office within 30 days.

API NUMBER 009-23,948
 LEASE NAME CLARK
 WELL NUMBER 2-19
4950 Ft. from S Section Line
4950 Ft. from E Section Line
 SEC. 19 TWP. 20 RGE. 14 (Star) (W)
 COUNTY WARTON
 Date Well Completed 7-9-85
 Plugging Commenced 5-13-96
 Plugging Completed 5-14-96

8-7-96
 15.009.23231.0001

LEASE OPERATOR NORTH STAR INVESTMENTS, INC.
 ADDRESS 13735 PINNACLE, WICHITA, KS 67230
 PHONE (316) 733-8997 OPERATORS LICENSE NO. 30601

Character of Well SAND
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on MAY 14, 1996 (date)

by RICK HESTERMAN (XCC District Agent's Name)
 Is ACO-1 filed? yes if not, is well log attached? _____

RECEIVED
 KANSAS CORPORATION COMMISSION
 JUL 13 1996

Producing Formation N/A Depth to Top _____ Bottom _____
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD CONSERVATION DIVISION
 WICHITA, KS

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	883'	NONE
				5 1/2	3,751	1805'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
SAND FILL BOTTOM OF HOLE W/ APPROX. 100 SKS SAND (NO FILL)
SET CIBP @ 3663 W/ 5 SKS CEMENT ON TOP. CUT CASING @ 1804
PULLED 3 JOINTS CASING + CEMENTED W/ 120 SKS 60/40 POSMIX + 500 LBZ HULLS.
PULLED 12 JOINTS TO 424', DUMPED 75 SKS CEMENT (60/40 POSMIX) CEMENT CIRCULATED.
PULLED LAST 11 JOINTS 5 1/2" + FILLED SURFACE TO TOP W/ 60/40 POSMIX, 500 LBZ CEMENT IN CELLAR TO TOP OFF.

Name of Plugging Contractor LIEKOR WELL SERVICE License No. 30891
 Address 1200 TRUMAN, GREAT BEND, KS 67530
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: NORTH STAR INVESTMENTS, INC.
 STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Dan Betting AGENT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Dan Betting
 (Address) 13735 PINNACLE WICHITA, KS 67230-1540

SUBSCRIBED AND SWORN TO before me this 19 day of July, 1996
Denice R. Robinson
 Notary Public

My Commission Expires: 9-27-99

