

STATE OF KANSAS
CORPORATION COMMISSION
S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

15.009.23948.0000

API NUMBER 15 009 23,948

LEASE NAME Clark

WELL NUMBER 1-19

2310 Ft. from X^N Section Line

330 Ft. from X^W Section Line

SEC. 19 TWP. 20 SRGE. 14 (E) or (W)

COUNTY Barton

Date Well Completed 11-12-96

Plugging Commenced 11-11-96

Plugging Completed 11-12-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Northstar Investments, Inc.

ADDRESS 13735 Pinnacle Wichita, Ks. 67230-1545

PHONE(S) (316) 733-8997 OPERATORS LICENSE NO. 30.601

Character of Well Oil

(i.e., Gas, D&A, SWD, Input, Water Supply Well)

A plugging proposal was approved on 11-8-96 (date)

by Herb Deines (XCC District Agent's Name).

ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3760

Give depth and thickness of all water, oil and gas formations.

L. GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	883	
				5 1/2	3751	1944

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Sanded bottom to 3209'. Bailed 5 sacks of cement. Shot pipe at 2613'. Shot 2055. Shot 2312. Shot 1940'. Pulled to 16025'. Pumped 115 sacks of cement. Pulled to 925'. Pumped 40 sacks of cement. Pulled to 440'. Circulated cement with 90 sacks. Pulled the rest of the pipe out. Topped off with 15 sacks.

Name of Plugging Contractor Quality Well Service Inc. License No. 31925

Address 249 East Beth Drive Sterling, Ks. 67579

RECEIVED
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: North Star Investments

STATE OF Kansas COUNTY OF Sedgwick, ss.


JAN 28 1997
1-28-97

Dean Britting (Employee of Operator) (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed that same are true and correct, so help me God.

(Signature) Dean Britting

(Address) 13735 Pinnacle Wichita Ks. 67230-1545



SUBSCRIBED AND SWORN TO before me this 28th day of January, 19 97

Shari L. Schulte
Notary Public

My Commission Expires: 4-13-97

USE ONLY ONE SIDE OF EACH FORM