

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County, Sec. 19 Twp. 20 Rge. 11W (E) (W)

Location as "NE/CNWxSWx" or footage from lines NW NE SW

Lease Owner L. Silver & Sons

Lease Name Schmidt Well No. 2

Office Address Box 921 Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) depleted Oil

Date well completed March 8, 19 50

Application for plugging filed May 15, 19 62

Application for plugging approved May 15, 19 62

Plugging commenced May 17, 19 62

Plugging completed May 17, 19 62

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation Depth to top Bottom Total Depth of Well 3702 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

10 3/4" 889' Cwc.
Sanded hole back to 3385' & dumped 5 sacks cement with dump bailer.
Pulled pipe. Mudded hole to 350', set bridge, & dumped 6 yds.
Ready-mix cement on bridge, cementing from 350' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
7-17-64
JUL 17 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Box 304 Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Z. Silver
2552 N. Belmont, Wichita, Kan
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 1964

My commission expires Dec. 9, 1965
Notary Public.

15.009.07162.0000

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **MAGNOLIA PETROLEUM CO.**

SEC. 19 T. 20 R. 14W
 LOC. NW NE SW

FARM **Schmidt Heirs** NO. 2

TOTAL DEPTH **3738' K.B.**

COUNTY **Barton**
 KANSAS


COMM. **2-17-50**

COMP. **3-8-50**

SHOT OR TREATED

CONTRACTOR **Mallonee Drig. Co.**

ISSUED **4-22-50**



CASING

20 10 3/4 889' w/500 sz cem.
 15 8
 12 6
 19 5 1/2 3737' w/250 sz cem.

ELEVATION

PRODUCTION **75 BO & 200 BWFH**

sand 80
 yellow clay 105
 shale 220
 shale, lime shells 300
 shale 445
 sand 470
 shale 470
 red bed, shale 570
 shale, lime shells 790
 red bed, shells 855
 red bed, shale 877
 gypsum 880
 anhydrite 908
 red bed, shale 1190
 shale, shells 1800
 slat, shale 1820
 lime, shale 1910
 sdy lime 2025
 sdy lime, shale 2070
 lime, shale 2170
 shale 2195
 lime, shale 2300
 shale, shells 2405
 brkn lime 2500
 shale, lime 2825
 brkn lime 2875
 shale 2905
 lime, shale 2955
 brkn lime 3055
 lime, chert 3089
 sdy lime 3196
 lime 3235
 brkn lime 3290
 shale 3325
 lime 3579
 sdy lime, shale 3610
 lime 3738
 Total Depth K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS:

DST #3 - 3650-53, op. 1 hr.,
 rec. 720' sylphur wtr., sl.
 show oil. BHP 1112#.

RECEIVED
 STATE CORPORATION COMMISSION

MAY 15 1962

CONSERVATION DIVISION
 Wichita, Kansas

TOPS: K.B.
 Heebner 3223 K.B.
 Lansing 3222
 Conglomerate 3564
 Simpson 3577
 Apbuckle 3604

DST #1 - 3337-43, op. 1 hr.,
 rec. 10' mud, no show.

DST #2 - 3634-38, op. 1 hr.,
 est. 100 MFCPD, rec. 510'
 oil, 690' slaty wtr.