

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 19 Twp. 20S Rge. 14W-E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C-SW SE


Lease Owner George R. Jones
Lease Name Habiger Well No. 1
Office Address 125 N. Market - Suite 1310, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole

Date Well completed April 15, 1980
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced April 15, 1980
Plugging completed April 15, 1980
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane L. Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,600'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	883'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,600 ft. (rotary total depth) to 800 ft. Set plug at 800 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 800 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 10 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4½ inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent (~~employee of owner~~)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of April, 1980

My commission expires July 25, 1982

Elsie Willison Notary Public.
STATE CORPORATION COMMISSION

APR 30 1980
4-30-80

CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY George R. Jones

SEC. 19 T. 20S R. 14W

FARM Habiger NO. 1

SEC. C-SW SE

COUNTY Barton

ROTARY TOTAL DEPTH 3,600'

COMM. April 7, 1980

COMP. April 15, 1980

CONTRACTOR H-30, INC. (Rig #11)

ISSUED April 28, 1980

CASING

10 3/4"

8 5/8" Set at 883' cemented w/125 sxs cement

ELEVATION 1,908' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	848'
Anhydrite	871'
Shale	2,235'
Lime and Shale	3,164'
Lime	3,600'
Rotary Total Depth	3,600'


I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 28th day of
April, 1980.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

