

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County. Sec. 19 Twp. 20 Rge. 11W (E) (W)

Location as "NE/CNWxSWx" or footage from lines SE SW SW

Lease Owner L. Silver & Sons

Lease Name Schmidt Well No. 4

Office Address P. O. Box 921 Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) depleted oil

Date well completed August 12, 19 53

Application for plugging filed May 15, 19 62

Application for plugging approved May 15, 19 62

Plugging commenced May 19, 19 62

Plugging completed May 19, 19 62

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3680 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8 5/8" 918' Cwc.
Sanded hole back to 3375' & dumped 5 sacks cement with dump bailer.
Pulled pipe. Mudded hole to 430', set rock bridge (30') & dumped
6 yds. Ready-mix cement on bridge, cementing from 400' to base of
cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 17 1964

7-17-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Box 304 Chase, Kansas

STATE OF Kansas, COUNTY OF Adgwick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. M. Silver
2552 N. Belmont, Wichita, Kan
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 64

My commission expires Dec 9, 1965
Jerry R. Rich Notary Public.

15 009 0033 (0000)


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM COMPANY
Farm- Schmidt Heirs No. 4

SEC. 19 T. 20 R. 11W
SE SW SW

Total Depth. 3680 PB 3648
Comm. 7-7-53 Comp. 8-12-53
Shot or Treated: Acidized
Contractor. Mallonee Drilling Co.
Issued. 10-24-53

County Barton
KANSAS



Elevation. 1914 D.F.

Production. P. 50 BO & 50 BHPD

CASINO:

9 5/8" 918' cem w/400 sx
5 1/2" 3678' cem w/200 sx

Figures indicate Bottom of Formations.

sand	70
shale, pyrite stks	230
shale	335
sand	430
red bed	625
red bed, shale	730
shale	867
chalk, shale	914
anhydrite	940
shale, shells	1300
shale, limeshells	1780
lime	1810
lime, shale	1975
lime	2100
shale	2121
lime	2260
lime, shale	2300
shale, lime shells	2500
lime, shale	3040
lime	3247
shale	3305
lime	3572
chert, shale, sand	3585
lime	3602
lime cherty, shale	3620
lime	3680
Total Depth	
PB 3648	

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1962

CONSERVATION DIVISION
Wichita, Kansas

Tops:

Heebner	3216
Lansing Kansas City	3314
Viola	3553
Arbuckle	3621

DST 3590-3602, op. 1 hr,
no blow, rec. 5' mud, BHP zero.

DST 3628-38, op., 35 min., gas
in 2 min., est. 1,600 MCFGPD,
oil & water spray 17 min.,
rec. 180' clean oil, 120' 50%
oil cut water, 540' sl. oil cut
water, 20 min. SI BHP 1085#.

Perf. 3587-92 w/24 sh., hydrafrac,
acidized w/250 gals., swb 10 BHP
dor 5 hrs., NSO.
Sq. perf. 3587-92, drld out cem. to
3648
Perf. 3630-33 w/12 jet sh., acidized
w/250 gals. P 15 BO & 100 BW in 15
hrs.