


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barton County. Sec. 19 Twp. 20 Rgs. 14 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner: Clinton Oil Company
Lease Name: Habiger #1 Well No.
Office Address: Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 1/27/73 19____
Plugging completed 1/31/73 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	862	none
				5 1/2"	3669	2097'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Shot pipe at 3869', 2714', 2508', 2282', 2089', pulled 65 joints.
Bailed hole to take head off and swedge well in. Pumped 3 sacks hulls,
20 sacks gel and 100 sacks pozmix. Shut well in with 200 lbs. pressure.

PLUGGING COMPLETE

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1973
CONSERVATION DIVISION
Wichita, Kansas

(if additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: KNIGHT CASING PULLING CO., INC.
Address: CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of February, 1973

MARGARET F. ELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975



Margaret F. Elcher
Notary Public.

DRILLERS LOG

VICTOR HABIGER NO. 1-V

CASING RECORD:	OPERATOR:	Clinton Oil Company	DESCRIPTION:
8-5/8" @ 862' w/450 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	SW SW SE Sec. 19-20S-14W Barton Co., Kansas
TOTAL DEPTH: 3670'	COMMENCED:	November 25, 1969	ELEVATION: 1907 KB
	COMPLETED:	December 6, 1969	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	65	
Clay	65	125	
Blue Shale	125	295	
Dakota Sand	295	385	
Red Bed	385	475	
Red Bed, Shale & Shells	475	863	
Anhydrite	863	880	
Red Bed	880	1135	
Shale, Shells & Sandy Lime Streaks	1135	1735	
Shale & Lime	1735	1965	
Lime & Shale	1965	2500	
Shale & Lime	2500	2975	
Lime & Shale	2975	3325	
Lime	3325	3490	
Lime & Shale	3490	3580	
Lime & Arbuckle	3580	3600	
Arbuckle	3600	3670	

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1972
CONSERVATION DIVISION
Wichita, Kansas

5 1/2" @ 3669/125 sax

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 8th day of December, 1969.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.