

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Ray Barton County, Sec. 1 Twp. 20 Rge. 13 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SW SW
Lease Owner Chief Drilling Co., Inc.
Lease Name Rogers Well No# 1
Office Address Box 797 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed yes 19____
Application for plugging approved yes 19____
Plugging commenced 7-21-60 19____
Plugging completed 8-25-60 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3465' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>5 1/2"</u>		<u>2,884'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 7-21-60. Plugging complete 7-25-60. Measured into total depth, 3465'. Plugged off bottom: Pushed plug to 3230', put in 20' of sand and dumped 5 sacks of cement. Worked and shot casing. Shot 5 1/2" casing free at 2884'. MIXED after spotting 60 barrels of oil. Built rack and slide. Pulled and laid down casing. Squeezed well: Mixed and pumped in 20 sacks of mud and 80 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 12 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
J. O. Forbes
Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of July, 19 60

My commission expires December 8th, 1963

Kayann Jenkins
Kayann Jenkins
Notary Public.

15.009.04820.0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company- CHIEF DRILLING COMPANY, INC., ETAL SEC. 1 T. 20 R. 13W
Farm- Rogers No. 1 SE SW SW

Total Depth. 3451'
Comm. 3-12-60 Comp. 3-22-60
Shot or Treated.
Contractor. Chief Drilling Co., Inc.
Issued. 9-17-60

County Barton
KANSAS



Elevation. 1834' DT

Production. Dry

CASING:

8 5/8" @ 240' w/200 sks. cem.
5 1/2" @ 3430' w/100 sks. cem.

Figures Indicate Bottom of Formations.

sand & shale	240
shale	260
red bed	430
sand	500
sand & red bed	665
Anhydrite	680
red bed	880
shale & shells	1580
lime	1955
shale & lime	2560
lime	2660
shale	2710
lime	3060
shale & lime	3095
shale	3175
lime	3410
shale	3422
Dolomite	3440 RTD
Dolomite	3451
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1964
CONSERVATION DIVISION
Wichita, Kansas

TOPS:

SCOUT
TOPS

Anhydrite	663	
Topeka	2712	
Heebner	3055	3059
Toronto		3074
Douglas		3093
Brown Lime	3172	3177
Lansing-Kansas City	3184	3192
Base Kansas City	3408	3413
Arbuckle	3421	3422