


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Pawnee County, Sec. 4 Twp. 20S Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines 150' NW of C SW NW
Lease Owner O. A. Sutton
Lease Name Miller Well No. 1
Office Address 800 Sutton Place, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 13 1969
Application for plugging filed August 13 1969
Application for plugging approved August 13 1969
Plugging commenced August 13 1969
Plugging completed August 13 1969
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 4382 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	283'	
RECEIVED STATE CORPORATION COMMISSION AUG 21 1969 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spot 1st plug @ 625' with 25 sacks Pozmix; Spot 2nd plug @ 275' with 25 sacks Pozmix; Spot 3rd plug @ 40' with 13 sacks Pozmix. Bridge rat hole with 2 sacks. Job by Howco.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack G. Paulsen (employee of owner) ~~OWNER~~ ~~OPERATOR~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Jack G. Paulsen
800 Sutton Place, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of August, 1969.
Jean S. Taylor
Notary Public.

My commission expires June 28, 1970.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

MILLER #1
C SW NW Section 4-20S-20W
Pawnee County, Kansas

Commenced: August 2, 1969
Completed: August 13, 1969

OPERATOR - O. A. Sutton

DEPTH		FORMATION	REMARKS
From	To		
0	215	Surface clay, shale and shells	
215	835	Shale and shells	Ran 14 joints of 8-5/8" casing, set @ 283' w/180 sacks cement.
835	1035	Sand	
1035	1400	Red bed, shale and shells	
1400	1428	Anhydrite	
1428	1485	Shale and shells	
1485	1860	Shale	
1860	3898	Lime and shale	
3898	3970	Lime	
3970	4178	Lime and shale	
4178	4382	Lime	
4382	TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1969
CONSERVATION DIVISION
Wichita, Kansas

I, JAMES S. SUTTON II, certify this is a correct copy of the Drillers' Log for the well drilled in the C SW NW, Section 4-20S-20W, Pawnee County, Kansas, to the best of my knowledge and belief.

James S. Sutton II
JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 19 day of August, 1969, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Barbara J. Layton
Barbara J. Layton, Notary Public

My Commission Expires Feb. 1, 1972.

