


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

Ness County. Sec. 34 Twp. 20S Rge. (E) 23 (W)

Location as "NE/CNWxSWx" or footage from lines C/NE NW  
Lease Owner Okmar Oil Company  
Lease Name Byron Well No. 1  
Office Address 1130 Wichita Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 13 1970  
Application for plugging filed August 13 1970  
Application for plugging approved August 13 1970  
Plugging commenced August 13 1970  
Plugging completed August 13 1970  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo J. Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4410 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	281'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole as follows: Plugged at 540' with 70 sacks of 50-50 pozmix; plugged at 270' with 20 sacks of 50-50 pozmix; plugged at 40' with 10 sacks of 50-50 pozmix. Plug down at 4:15 A. M. August 13, 1970.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 19 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Charles W. Steincamp (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
Charles W. Steincamp, President  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

Subscribed and sworn to before me this 14th day of August, 19 70  
Elaine H. Taylor  
Elaine H. Taylor Notary Public



My Commission Expires December 14, 1973

DRILLERS LOG

#1 Byron

CASING RECORD:  
281' of new 8-5/8"  
surface casing.

COMPANY: Okmar Oil Company  
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/NE NW  
Section 34-20S-23W  
Ness County, Kansas

TOTAL DEPTH:  
4410'

COMMENCED: August 3, 1970  
COMPLETED: August 13, 1970

ELEVATION: 2220' KB

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Sand & Post Rock	0	307	Ran 281' of new 8-5/8" surface casing; set and cemented at 288' with 170 sacks of regular cement, 2% gel and 3% C. C. Plug down at 10:45 P. M. August 3, 1970.
Shale w/Sand Streaks	307	550	
Red Bed, Shale w/Sand Streaks	550	775	
#1 Anhydrite	775	792	
Red Bed, Shells & Shale	792	1406	
#2 Anhydrite	1406	1430	
Shale & Shells	1430	1583	
Red Bed, Broken Lime & Shale	1583	1827	
Shale & Lime	1827	3880	
Lime	3880	4106	
Lime & Shale	4106	4205	
Lime	4205	4360	
Lime, Chert & Shale	4360	4395	
Lime & Chert	4395	4410	

Rotary Total Depth: 4410'

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 19 1970  
CONSERVATION DIVISION  
Wichita, Kansas

D. & A.

Plugged hole as follows: Plugged at 540' with 70 sacks of 50-50 pozmix; plugged at 270' with 20 sacks of 50-50 pozmix; plugged at 40' with 10 sacks of 50-50 pozmix. Plug down at 4:15 A. M. August 13, 1970.


STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 14th day of August, 1970.



*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public