


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Barton County. Sec. 36 Twp. 20S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SW NW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name ALDRICH Well No. 1
Office Address 800 Bitting Building, Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed August 7, 1962 19
Application for plugging filed December 12, 1962 19
Application for plugging approved December 12, 1962 19
Plugging commenced December 12, 1962 19
Plugging completed December 15, 1962 19
Reason for abandonment of well or producing formation non-productive in commercial quantities
If a producing well is abandoned, date of last production November 9, 1962
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Lansing-KC Depth to top 3241 Bottom 3470 Total Depth of Well 3525 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					8X8X8X	
				8 5/8"	260'	cemented
				5 1/2"	3524	2751'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 3300 feet and ran 4 sacks of cement from 3300 feet to 3275 feet. Mudded from 3275 feet to 260 feet - rock bridge from 260 feet to 250 feet - ran 25 sacks of cement from 250 feet to 175 feet - mudded 175 feet to 35 feet rock and 10 sacks of cement to base of cellar

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1963

3-2663

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn and Smith Pipe Pulling Company
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul

800 Bitting Building, Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of January, 1963.

Virginia Marshall
Notary Public.

My commission expires August 10, 1965



WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: July 16, 1962

Contractor: Quaker Drilling Co., Inc.

Completed: July 24, 1963

Aldrich No. 1
SE SW NW Sec. 36-20S-13W
Barton County, Kansas

Elevation: 1870 K.B.

Casing Record

Set 8 5/8 inch casing at 260 feet with 250 sacks cement
Set 5 1/2 inch casing at 3524 feet with 125 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil and Sand	220	Heebner	3105 -1235
Shale and Pyrite	285	Brown Lime	3226 -1356
Red Bed	692	Lansing	3241 -1371
Anhydrite	710	Base of Kansas City	3470 -1600
Shale and Shells	1610	Conglomerate	3477 -1607
Lime and Shale	2245	Rotary Total Depth	3525 -1655
Shale	2685		
Lime and Shale	2825		
Lime	3040		
Lime and Shale	3231		
Lime	3470		
Cherty Lime	3525		

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1963

CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the driller's log of the well drilled in the SE SW NW Section 36, Township 20 South, Range 13 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul

SUBSCRIBED AND SWORN to before me a Notary Public this 20th day of August, 1962.

Virginia Mundell
Virginia Mundell, Notary PublicMY COMMISSION EXPIRES:
August 10, 1965