


Give All Information Completely
Make Required Affidavit
Mail or Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Barton County. Sec. 36 Twp. 20S Rge. 13 (00) (W)
Location as "NE/CNW/SW" or footage from lines SW SE NW
Lease Owner Welch & Olsson Drilling Company, Inc.
Lease Name Aldrich Well No. 1
Office Address 1017 Union National Bank Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 12-29 19 53
Application for plugging filed 12-29 19 53
Application for plugging approved 12-29 19 53
Plugging commenced 12-29 19 53
Plugging completed 12-29 19 53
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, 2341 Washington, Great Bend, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	260'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 200'. Set wooden plug. Cemented and displaced 20 sacks
of cement through drill pipe onto plug. Mudded to 40' and set second
plug. Filled hole to bottom of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Welch & Olsson Drilling Company, Inc.
Address 1017 Union National Bank Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. E. Welch

(~~owner or operator~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____


(Address) _____

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 54

Marcella H. Davis

My commission expires Feb. 27, 1956.

Notary Public.



2-17-54

WELL LOG

WELCH & OLSSON DRILLING CO., INC.

Elevation: 1864' K. B.

CONTRACTOR: Welch & Olsson Drilling Co., Inc.

Commenced: 12-17-53

Aldrich No. #1

Completed Drig: 12-29-53

SW SE NW Sec. 36,

Twp. 20S, Rge. 13W,

Barton County, Kansas.

Production: D & A

casing record:

Set 260' of 8-5/8" with 225 sacks of cement.

(Figures indicate bottom of Formations)

<u>FORMATIONS:</u>	<u>DEPTHS</u>	<u>FORMATION TOPS</u>	
Surface, Soil & Sand	190'	Heebner	3092 - 1228'
Sand	215'	Brown Lime	3216 - 1352'
Pyrite	228'	Lansing - K.C.	3232 - 1368'
Shale & Sand	260'	Base - K. C.	3452 - 1588'
Red Bed	690'	Conglomerate	3481 - 1617'
Anhydrate	705'	Arbuckle	3583 - 1719'
Shale & Shells	1635'		
Shale	1860'		
Lime & Shale streaks	1975'		
Lime & Shale	2130'		
Lime	2210'		
Shale & Shells	2660'		
Lime	3107'		
Lime & Shale	3220'		
Lime	3505'		
Chert	3583'		
Lime	3600' T.D.		

STATE OF KANSAS

COUNTY OF SEDGWICK, SS:

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the SW SE NW, Section 36, Township 20S, Range 13W, Barton County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.

By: H. E. Welch

H. E. Welch

Subscribed and sworn to before me this 8th day of January, 1954.

Marcella A. Davis
Notary Public

My Commission Expires: Feb. 27, 1956.

