

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 2 Twp. 20 Rge. 16 (E) W (W)

Location as "NE/CNW&SW" or footage from lines NW NE, NW

Lease Owner Specter & Morgenstern

Lease Name Nelson Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 5-1-45 19

Application for plugging filed 2-12-55 19

Application for plugging approved 2-14-55 19


Plugging commenced 2-15-55 19

Plugging completed 2-22-55 19

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production February 1955

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Arbuckle Depth to top 3655 Bottom 3765 Total Depth of Well 3765 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	1005'	None
				5 1/2" OD	3764 1/2'	2689'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging started 2-20-55 and completed 2-27-55. Filled back with rock to 3715' and dumped 5 sacks of cement, with bailer. Shot casing off at 3765' and pulled pipe out of hole. Filled hole with heavy mud to 300'. Set permanent rock bridge at 300' and dumped 20 sacks of cement with bailer. Filled hole with heavy mud to 35' of top, set permanent rock bridge and dumped 10 sacks of cement with bailer for cap on well.

RECEIVED
STATE CORPORATION COMMISSION
MAR 10 1955
CONSERVATION DIVISION
WICHITA, KANSAS

3-10-55

Name of Plugging Contractor Forbes Casing Pulling Co. (If additional description is necessary, use BACK of this sheet)
Address Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss. Morton Specter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morton Specter
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 9th day of March 1955

My commission expires Dec 1, 1955 Notary Public.

PLUGGING
FILE SEC 2 T20 R16W
BOOK PAGE 97 LINE 31

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas


15.145.01215.0000

Company - GULF OIL CORP.
Farm # Matilda Nelson No. 1

SEC. 2 T. 20 R. 16 W
NW NE NW

Total Depth. 3765' PB 3748'
Comm. 2-19-45 Comp. 5-1-45
Shot or Treated. 4-19-45 500 gals.
Contractor.
Issued. 6-16-45

County. Pawnee
KANSAS



CASING:

8 5/8" 1005' Cem.
5 1/2" 3764 1/2' Cem.

Elevation. _____

Production. Pot. 2911 BO, no W.
6,598,400 G.

Figures Indicate Bottom of Formations.

sand	0-110
sand & shale	287
shale & lime shells	315
shale & shells	427
sand	565
shale	570
sand & shale	600
sand	625
red bed & sand & shale	690
shale & red bed	760
sand & red bed	810
shale & shells	973
red bed, sand & anhydrite	1015
anhydrite	1045
shale & shells	1300
shale & shells & salt	1450
salt & shale	1570
shale, lime shells & sand	1770
shale & shells	1810
lime brkn	2055
lime & sdy lime	2145
lime	2410
sand & lime	2445
shale & shells	2515
shale & lime	2575
shale & lime shells	2845
shale & lime	3105
lime, shale & lime	3180
lime & shale	3214
lime & sand	3273
lime	3490
lime & chert	3516
lime	3621
lime & shale	3675
lime	3765
Total Depth.	

Plugged back to 3748'

Tops:

Heebner	3307
Toronto	3323
Douglas Shale	3338
Lansing - K.C.	3382
Marmaton	3627
Arbuckle	3655

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
WELL SEC 2 T 20 R 16 W
BOOK PAGE 97 LINE 31