

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Rice

County. Sec. 21 Twp. 20S Rge. (E) 9 (W)Location as "NE/CNW/SW" or footage from lines SW NW NWLease Owner Dallas Uranium & Oil CorporationLease Name McGlynnWell No. 1Office Address 501 Elm, Dallas TexasCharacter of Well (completed as Oil, Gas or Dry Hole) Dry HoleDate well completed 11/28 19 59Application for plugging filed 11/28 19 59Application for plugging approved 11/28 19 59Plugging commenced 11/28 19 59Plugging completed 11/28 19 59Reason for abandonment of well or producing formation Dry HoleIf a producing well is abandoned, date of last production 19Was permission obtained from the Conservation Division or its agents before plugging was commenced? yesName of Conservation Agent who supervised plugging of this well Gilbert TomanProducing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3355 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	165'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud Bottom plug @ 155' with 20
sacks cement filled to 40' plug @ 40' with 10 sacks cement
2 sacks cement in rat hole

STATE CORPORATION COMMISSION

DEC 4 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol, Inc.Address 414 Union Center, Wichita, KansasSTATE OF Kansas, COUNTY OF Sedgwick, ss.Warren E. Tomlinson

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Warren E. Tomlinson414 Union Center, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 12nd day of December, 19 59My commission expires Jan. 19, 1961

Notary Public.

DRILLERS LOG
DALLAS URANIUM & OIL CORP.
 # 1 McGLYNN
 SW NW NW, SEC. 21-20S-9W
 RICE COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Commenced: 11/20/59
 Completed: 11/28/59
 Elevation: 1769 KB

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	68	Clay	
147	162	Lime & Shell	165' 8-5/8" 4/125 sacks
162	1175	Shale	
1175	1345	Anhydrite	
1345	1554	Shale & Lime	
1554	1580	Sand	
1580	1840	Shale	
1840	1888	Lime & Shale	
1888	2034	Lime	
2034	2232	Lime & Shale	
2232	2383	Shale & Lime	
2383	2747	Lime & Shale	
2747	2841	Lime	
2824	2935	Shale	
2935	3014	Lime - Shale	
3014	3293	Lime	
3295	3336	Shale & Sand	Heebner 2829
3336	3346	Shale	Brown Lime 2961
3346	3353	Arbuckle	Lansing 2985 -1216
			Simpson 3322
			Arbuckle 3355 -1586
			RTD 3355

RECEIVED
 STATE CORPORATION COMMISSION

DEC 4 1959

CONSERVATION DIVISION
 Wichita

I certify to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

Warren E. Tomlinson
 Warren E. Tomlinson

State of Kansas)

County of Sedgwick)

Subscribed and sworn to before me this 2nd day of December, 1959.

Esther L. Lamm
 Notary Public

My Commission Expires Jan. 19, 1961