


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

**WELL PLUGGING RECORD**

Rice County, Sec. 21 Twp. 20 Rge. 9E (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE  
Lease Owner Apex Supply Co.  
Lease Name Dick #1 Well No. \_\_\_\_\_  
Office Address Great Bend, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 10-28-59 19\_\_\_\_  
Plugging completed 11-4-59 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toamn  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3277 Feet  
Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	167'	none
				5-1/2"	3275'	2442'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole, found parrafin bridge at 800'. Put in 40 gallons of Kerosene and got bridge out. Hole open to 3277'. Filled w/sand to 3260' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing. Cleared hole and mudded the hole to 210', set rock bridge to 200' and dumped 25 sacks of cement, filled to 125'. Mudded the hole from 125' to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION

PLUGGING COMPLETED

NOV 16 1959

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co. CONSERVATION DIVISION  
Address Chase, Kansas Wichita, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of November, 19 59

My commission expires 9-27-62


Thomas V. Duggs  
Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg. Wichita, Kansas

Company - DERBY DRILG. CO.  
Farm - Dick No. 1

SEC. 21 T. 20 S. 9 E.  
NW 1/4 NE

Total Depth. 3275 D.F.  
Comm. 10-24-47 Comp. 11-7-47  
Shot or Treated. None  
Contractor. Derby Drilg. Co.  
Issued. 7-24-48

County. Rice  
KANSAS  


CASING:  
3-5/8" 167' Cem. 1/150 Sx.  
5-1/2" 3275' Cem. 1/100 Sx.

Elevation. \_\_\_\_\_  
Production. 75 BO'D

Figures Indicate Bottom of Formations.

soil	10
sand	142
red rock & shells	168
red rock	330
lime, shells & shale	480
shale & salt	1160
shale & shells	1357
lime & shale	1735
lime	1926
shale & lime	2088
shale & shells	2300
lime	2755
lime & shale	2952
lime	3277

3277' = 3275' D.F.  
Total Depth

Tops: (DFM)

Brown Lime	2908
Lansing K. C.	2934
gathered Simpson	3246
Simpson Sand	3267
gathered Arbuckle	3271
True Arbuckle	3273