


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 24 Twp. 20 Rge. 11 9 (W)
Location as "NE/CNW/SW" or footage from lines SW SE
Lease Owner Carl Lebsack
Lease Name Schwamborn Well No. 1
Office Address Box 479 Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 15, 19 62
Application for plugging filed April 15, 19 62
Application for plugging approved April 15, 19 62
Plugging commenced April 15, 19 62
Plugging completed April 15, 19 62
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug 225' with 1/2 sack of hulls and mixed 25 sacks of cement & poured through drill pipe. Set top plug at 30' and mixed 8 sacks of cement and mixed 2 sacks for rat hole.

Under the supervision of Cecil Jones
McPherson, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1962

5-1-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ISERN DRILLING COMPANY
Address Box 486 Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Richard Hogg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. H. Hogg
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of April, 1962

My commission expires February 10, 1963
George A. Meyer (Notary Public)



WELL LOG

Carl Lebsack, Schwamborn #1
 SW SE Section 24-20-9
 Rice County, Kansas

Figures indicate bottom of formation:

ELEVATION: 1678 KB	0	to	10	cellar
			60	sand
PIPE RECORD:			228	Shale & shells
			250	red bed
8 5/8" set at 228 with			850	shale & shells
200 sacks of cement.			1050	salt
			1165	shale & shells
Rotary commenced: 4-6-62			1275	shale & lime
Rotary completed: 4-15-62			1480	shale & shells
			1515	shale & lime
GEOLOGICAL TOPS:			1800	lime & shale
Heebner 2732			2310	shale & shells
Brown Lime 2871			2620	shale & lime
Lansing 2906			3040	lime & shale
Viola 3386			3083	lime
Simpson shale 3436			3225	lime & shale
Simpson sand 3440			3398	shale & lime
Arbuckle 3496			3436	lime & shale
			3496	sand & shale
			3500	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 1 1962
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF BARTON)

I, Dean Wells, Partner of Isern Drilling Company, the drilling contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

Dean Wells

 Dean Wells

Subscribed and sworn to before me this 19th day of April, 1962.

I. J. Rader

 I. J. Rader, Notary Public

My Commission expires July 7, 1964.