


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 24 Twp. 20S Rge. (E) 9 (W)
Location, as "NE/CNW/SW" or footage from lines C NW NW NW
Lease Owner Sterling Drilling Company
Lease Name Fair "G" Well No. #1
Office Address Box 127, Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 15 19 62
Application for plugging filed August 15 19 62
Application for plugging approved August 15 19 62
Plugging commenced August 16 19 62
Plugging completed August 16 19 62
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3430 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					8 5/8 "	none
					196.55'	
					set at 205'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging orders by Mr. Gilbert Toman. Heavy mud up to 200'.
Halliburton plug at 200' 1/4 sack hulls on plug. 20 sacks cement
through drill pipe. Heavy mud up to 35' Halliburton plug at 35'
1/4 sack hulls on plug. 10 sacks cement up to base cellar 2 sacks
cement in rat hole. Plugging complete 6:30 a. m. 8-16-62

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1962

8-24-62

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Group Exploration Company
Address Box 127, Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

Olin Kelso, (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Olin Kelso

Sterling, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 62

My Commission Expires Jan. 22, 1966

BERNARD LAUDERMILK

Bernard Laudermilk
Bernard Laudermilk, Notary Public.

My commission expires

GROUP EXPLORATION COMPANY
Sterling, Kansas

WELL LOG -----Fair G #1
Located: C NW NW NW of Section 24-20S-9W, Rice County, Kansas

OWNER: Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 8-9-62
COMPLETED: 8-15-62

ROTARY TOTAL DEPTH: 3430'

LOG

- 0 - 190 Sand & Shale
- 190 - 1090 Shale & Shells
- 1090 - 1440 Shale & Lime
- 1440 - 1840 Lime
- 1840 - 2025 Lime & Shale
- 2025 - 2345 Shale
- 2345 - 2925 Shale & Lime
- 2925 - 3230 Lime
- 3230 - 3310 Lime & Shale
- 3310 - 3380 Lime & Sand
- 3380 - 3430 Shale & Lime

CASING RECORD

Set 8 5/8 " Surface casing @ 205'
with 175 sacks Pozmix HA-5.

Plugged and Abandoned.

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1962

CONSERVATION DIVISION
Wichita, Kansas