


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County. Sec. 24 Twp. 20 Rge. (E) 9 (W)
Location as "NE/CNW&SW" or footage from lines. E/2 E/2 NW/4
Lease Owner Sterling Drilling Company
Lease Name Fair "H" Well No. 1
Office Address Box 129, Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed March 3 19 70
Application for plugging approved 19
Plugging commenced May 16 19 70
Plugging completed May 19 19 70
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3330 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	228'	7"	228'	none
		0	3327'	4 1/2"	3327'	2532.31

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3300' and dumped 4 sacks of cement.

Set rock bridge from 228' to 200' and dumped 15 sacks of cement. Filled hole with mud to 40' and capped well with 5 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1970

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 19 70

My commission expires Feb. 10, 1971

George A. Meyer
Notary Public.

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- FAIR "H" #1

LOCATED: E/2 E/2 NW/4 Section 24-20S-9W, Rice County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 4, 1966

COMPLETED: September 12, 1966

ROTARY TOTAL DEPTH: 3330'

LOG

0 - 165	Sand & Gravel
165 - 232	Clay & Shale
232 - 1150	Shale & Shells
1150 - 1655	Shale & Lime
1655 - 1990	Lime
1990 - 2742	Lime & Shale
2742 - 2970	Sand & Shale
2970 - 3040	Shale & Lime
3040 - 3178	Lime
3178 - 3240	Limestone & Shale
3240 - 3260	Sand & Shale
3260 - 3330	Shale T.D.

CASING RECORD

Ran 7 joints 7" 20# used seamless casing, 217.31' pipe set at 228' K.B.. Cemented with 100 sacks Pozmix #1 with 2% NA-5. Plug was down at 1:30 a.m. 9-5-66.

Ran 104 joints 4-1/2" 9.5# J-55 8rd casing. Pipe set at 3327' with 75 cubic feet 50 - 50 Pozmix, 18% salt saturated. Pumped 15 barrels salt water ahead of cement. Plug down at 11:00 a.m.. Shoe joint 30.55', K.B. is 9.85' above braden head.

RECEIVED
STATE CORPORATION COMMISSION
MAR 4 1970
CONSERVATION DIVISION
Wichita, Kansas

2 1/2 Tubing cemented in! =
deepened to Simpson (130' in)