


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Rice County, Sec 24 Twp 20S Rge 9 (E) (W)
Location as "NE/CNW/SW" or footage from lines: SW SE SW
Lease Owner Thunderbird Drilling, Inc.
Lease Name Seitz Well No. 5
Office Address 706 Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 14 1963
Application for plugging filed November 14 1963
Application for plugging approved November 14 1963
Plugging commenced November 14 1963
Plugging completed November 14 1963
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrude, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3435 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled to 200' with heavy mud
Plug set @ 200' with 20 sacks cement
Hole filled to 40'
Set plug @ 40' with 10 sacks cement
2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Thunderbird Drilling, Inc.
Address 706 Union Center Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Charles W. Aikins, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Charles W. Aikins, Jr., President
706 Union Center Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 1963

My commission expires October 9, 1967

Priscilla L. Graham
Priscilla L. Graham Notary Public.



DRILLERS LOG

#5 Seitz

LOCATION: SW SE SW of Section 24,
Township 20 South, Range 9 West,
Rice County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.
706 Union Center Building
Wichita, Kansas

COMMENCED: November 7, 1963

COMPLETED: November 14, 1963

SURFACE CASING: 8-5/8" surface casing set at 205'
with 180 sacks cement, 1% gel,
3 sacks calcium chloride, 2 sacks
ammonia chloride.

ELEVATION: 1679' K. B.
1676' D. F.
1674' G. L.

WELL LOG:

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1963

CONSERVATION DIVISION
Wichita, Kansas

0 -	140	Sand
140 -	268	Red Bed
268 -	280	Anhydrite
280 -	350	Red Bed
350 -	1320	Shale and Shells
1320 -	1680	Lime and Shale
1680 -	2560	Shale and Lime
2560 -	2695	Lime
2695 -	2970	Shale and Lime
2970 -	3435	Lime
3435		Rotary Total Depth

The undersigned, Charles W. Aikins, Jr., an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #5 Seitz as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.

Charles W. Aikins, Jr., President

Subscribed and sworn to before me this 15th day of November, 1963.

Priscilla L. Graham
Priscilla L. Graham, Notary Public

My commission expires 10-9-67.