

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

Rice County. Sec. 24 Twp. 20 Rge. 9 (E) (W)

Location as "NE/CNW&SW" or footage from lines SW SW SW  
Lease Owner Thunderbird Drilling Company  
Lease Name Seitz #1 Well No.  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19.  
Application for plugging filed 19.  
Application for plugging approved 19.  
Plugging commenced 9/30/70 19.  
Plugging completed 10/6/70 19.  
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19.  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman

Producing formation Depth to top Bottom Total Depth of Well 2381 Feet 3368'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	210	none
				5 1/2"	3365	2381'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, had bridge at 2170', pushed out at 2170' to 3368', checked hole and ran sand to 3350', ran 5 sacks of cement. Dug cellar, took hedd apart, rigged up, shot pipe at 2603', worked pipe to 17" tension. Hooked up pump, tried to spot oil, had 1400 lb. pressure. Shot pipe at 2479', pumped 40 barrels oil and 62 water at 400 lb. pressure. Worked tension to 18", worked to 20", checked hole to 2380', shot pipe at 2380', worked pipe loose and pulled 75 joints. Bailed hole to 200', set 10' rock bridge and ran 25 sacks of cement. Mudded to 40', set 10' rock bridge and ran 10 sacks of cement. Tallied pipe.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 29 1970  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address Chase, Kansas 67524

STATE OF Kansas, COUNTY OF Rice, ss. Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel Knight*  
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of October, 1970

My commission expires 2/15/71 *Margaret Melcher* Notary Public.