

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-21,792

LEASE NAME Habiger

WELL NUMBER 1

SPOT LOCATION SW SE NE

SEC. 24 TWP. 20 RGE. 9 ~~050~~ or (W)

COUNTY Rice

Date Well Completed 2-25-84

Plugging Commenced 2-25-84

Plugging Completed 2-25-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Edwards Oil, Inc.

ADDRESS Box 206 Hutchinson, KS 67501

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Don Tomán
to be filed by _____

Is ACO-1 filed? operator If not, is well log attached? yes

Producing formation _____ Depth to top _____ bottom T.D. 3493

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 260' w/50 sacks cement thru drill pipe
Top Plug: @ 40' w/1 sack hulls and 10 sacks cement
10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929
Address Box 823 Great Bend, KS 67530

STATE OF kansas COUNTY OF Barton, ss.

Leonard Williamson (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
~~I have~~ I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well **RECEIVED** that the same are true and
correct, so help me God. STATE CORPORATION COMMISSION

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

MAR 02 1984

SUBSCRIBED AND SWORN TO before me this 27 day of Febr., 1984
Wichita, Kansas

Dorothy M. Hague
Notary Public

My Commission expires: 4-29-86

DRILLER'S WELL LOG

DATE COMMENCED: February 19, 1984
 DATE COMPLETED: February 25, 1984

Edwards Oil Inc.
 HABIGER #1
 SW SE, NE
 Sec. 24, T20S, R9W
 Rice County, Ks.

ELEVATION: 1676' K.B.

0 - 254' Surface Soil, Red Bed
 254 - 268' Anhydrite
 268 - 2371' Lime & Shale
 2371 - 2393' Lime
 2393 - 2409' Shale & Sand
 2409 - 2734' Lime
 2734 - 2738' Shale
 2738 - 2755' Lime & Shale
 2755 - 2764' Lime
 2764 - 2870' Shale
 2870 - 2901' Lime & Shale
 2901 - 3204' Lime
 3204 - 3493' Shale, Chert, Sand
 3493' RTD

FORMATION DATA

Anhydrite 254'
 Howard 2371'
 Severy 2393'
 Topeka 2409'
 Heebner 2734'
 Toronto 2755'
 Douglas 2764'
 Bri Lime 2870'
 Kansas City 2901'
 Base K.C. 3204'
 Kinderhook 3242'
 Maquoketa 3362'
 Viola 3398'
 Simpson 3434'
 RTD 3493'

Surface Pipe: Set new 8-5/8"
 20# pipe @204' w/195 sacks
 50/50 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss:

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 27 day of February 1984.

My Comm. Expires:

4-29-85

Deborah M. Blaque
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

MAR 02 1984

CONSERVATION DIVISION
 Wichita, Kansas