

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rice County, Sec. 24 Twp. 20 Rge. 9 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE, SE

Lease Owner Charles Hulme Drilling Co

Lease Name ~~Great Bend, Kansas~~ E. Roth Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-4-52 19 52

Application for plugging filed 1-4-52 19

Application for plugging approved 19


Plugging commenced 8 AM 1-4 19 52

Plugging completed 10 AM 1-4 19 52

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top 3455 Bottom 3455 Total Depth of Well 3455 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	178'	8-5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 27' feet to 178' feet for each plug set.

Used two Halliburton Plugs. Pushed to the depth of 178' cemented with 15-sacks cement, cemented through the drill pipe. Pushed top plug to 27-Feet cemented with 10-sacks cement.

JAN 11 1952

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: C.L. Tyrrell
Address: Box 542, Chase, Kansas.

STATE OF Kansas, COUNTY OF Rice, ss.
Hulme Drilling Co., (employee of owner) (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.E. Byars
14 Vivian St.
Great Bend, Kas.
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of January, 1952

My commission expires 3/1/55
Oswalds Miller
Notary Public.

PLUGGING
FILE SEC 24 T 20 R 9 W
BOOK PAGE 136 LINE 13

E. Rothwell
 SE 24-20-9W
 Rice County, Kansas

Date Commenced: December 22, 1951
 Date Plugged: January 4, 1952

Surface Pipe: 178' - 8 5/8" casing 150 sacks cement

0	165	Sand, Gravel and Clay
165	188	Red Bed
188	870	Red Bed, Shale and Shells
870	1059	Shale and Shells
1059	1255	Salt
1255	1275	Shale and Shells
1275	1510	Lime
1510	1840	Lime and Shale
1840	2020	Shale
2020	2325	Shale, Lime and Shells
2325	2455	Shale and Shells
2455	2680	Lime
2680	2810	Sandy Lime
2810	2880	Shale and Sandy Lime
2880	3060	Lime
3060	3260	Lime and Shale
3260	3265	Lime
3265	3310	Conglomerate
3310	3455	Lime and Shale
3455		D & A

JAN 12 1952

PLUGGING
 FILE SEC 24-20-9W
 BOOK PAGE 136 LINE 13