



15.145.20124.0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 14 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Gabbert of Gabbert & Jones has this

date requested permission to plug the following described well:

Mr. Gabbert guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton

Complete Address: 800 Sutton Place Wichita, Ks.

Lease Name: Miller Well No. 1

Location: 150' NW C SW NW Sec. 4 Twp. 20 Rge. 20 (E)(W) X

County: Pawnee Total Depth 4382 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Gabbert was instructed to plug the well as follows:

Gun pits, circulate heavy mud; set cementing plug at 625' and displace
25 sk cmt thru drill pipe. Heavy mud to 275' set cementing plug and
displace 25 sk cmt. Heavy mud to 40' set cementing plug, 1/2 sk hulls
and 10 sk cmt to base of cellar.

Very truly yours,

Leo P. Muesy
 Conservation Division Agent