



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1962

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Dwight J. Wilson of Alpine Oil & Royalty Co., has this date requested permission to plug the following described well:

Mr. Dwight J. Wilson guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Co.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name: Aldrich Well No. # 1

Location: SE SW NW Sec. 36 Twp. 20 Rge. 13 (E) (W)

County Barton Total Depth 3525 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. R. E. Smith was instructed to plug the well as follows:

8 5/8" 260' Cwc.
Sanded hole back to 3290' & dumped 4 sax cement with dump
bailer. Pulled pipe; bailed hole down to 260'; set rock
bridge, & displaced 25 sax cement. Mud to 40', set rock
bridge, & displaced 10 sax cement, cementing to base of
cellar.

Very truly yours,

Don Truman
Conservation Division Agent