



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

May 6, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Darrell Anderson of Duke Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: P. V. Properties, Inc.

Complete Address: 360 sutton Place, Wichita, Kansas 67202

Lease Name: Birchenough Well No. 1

Location: C W/2 NE SE Sec. 22 Twp. 20 Rge. 9 ~~(E)~~ (W)

County: Rice Total Depth: 3475'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Anderson was instructed to plug the well as follows:

8-5/8"-210'-175 sacks 60/40 pozmix w/2% gel and 3% cal chl.

Hole filled with mud. Pump 50 sacks 50-50 pozmix w/2% gel and 3% cal ch. through drill pipe at 480'. Pump 30 sacks cement through drill pipe at 240'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rahole with 5 sacks cement.

Orders by Marian Schmidt

Very truly yours,

Shirley D. Roman
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1981

CONSERVATION DIVISION
Wichita, Kansas