

NOV 28 1962

State of Kansas



15.159.02864.0000

FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 25, 1962

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Jones of Raymond Oil Co., Inc. has this

date requested permission to plug the following described well:

Mr. Jones guarantees payment of the plugging fee.

Operator's full Name: Muir-Thompson, Inc.

Complete Address: 201 Garlinghouse Bldg., 820 Quincy, Topeka, Kansas

Lease Name: Hoover Well No. 1

Location: SE SE SW Sec. 22 Twp. 20 Rge. 9 (W) X

County Rice Total Depth 3395' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Jones was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 190'. Push
plug and 1/4 sack hulls to 190' and cement with 20 sacks
thru drill pipe. Fill hole with mud to 35'. Push plug
and 1/4 sack hulls to 35' and cap hole with 10 sacks cement.
Fill, Bridge, and cement rathole with 2 sacks.

Very truly yours,

Conservation Division Agent