

State of Kansas



15.159.02635.0000

State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
NOV 29 1966
11-29-66
CONSERVATION DIVISION
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

November 22, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 6810 West Highway 54, Wichita, Kansas

Lease Name: Birchenough Well No. 4

Location: NE NE SE Sec. 22 Twp. 20 Rge. 9 (E) (W) X

County Rice Total Depth 3378' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3350' and cement with 5 sacks.

Fill hole with mud to 205'. Set rock bridge from 205' to 195' and

cement hole with 25 sacks. Fill hole with mud to 30'. Set rock bridge

from 30' to 20' and cap hole with 10 sacks cement.

Very truly yours,

William J. Loman
Conservation Division Agent