

State of Kansas



15.159.02632.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 8, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co, Inc has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 217 N. Water, Wichita, Kansas 67202

Lease Name: Birchenough Well No. 1

Location: SW NW SE SENESE Sec. 22 Twp. 20 Rge. 9 (W) X

County: Rice Total Depth 3376' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3360' and cement with 6 sacks cement.

Fill hole with mud to 200'. Set rock bridge from 200' to 190' and

cement hole with 35 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent