



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

May 18, 1972

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

5-25-72 MAY 25 1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Melvan Urban of Aladdin Petroleum Corp. has this date requested permission to plug the following described well:

Mr. Urban guarantees payment of the plugging fee.

Operator's full Name: Aladdin Petroleum Corporation

Complete Address: 809 Petroleum Bldg., Wichita, Kansas 67202

Lease Name: Shepherd Well No. 1

Location: 1320' E, of WL ADPC 5/2 NE
440' N. of SL --NE/4 Sec. 32 Twp. 20 Rge. 9 (E) (W) X

County: Rice Total Depth 3341' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Urban was instructed to plug the well as follows:

Fill hole with mud to 265'. Push plug and 1/4 sack hulls to 265' and cement
hole with 25 sacks cement through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Richard J. Roman
Conservation Division Agent