

State of Kansas



JOHN ANDERSON, Jr. Governor  
 WILLIAM L. MITCHELL Chairman  
 ALVIN P. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

August 11, 1965 RECEIVED  
 STATE CORPORATION COMMISSION

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

AUG 17 1965  
 8-17-65  
 CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Lebsack Oil Production Company

Complete Address: P.O. Box 489, Hays, Kansas

Lease Name: Schuler Well No. 1

Location: NW SW SE Sec. 11 Twp. 20 Rge. 9 (E) (W) X

County Rice Total Depth 3388' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 5 sacks.

Fill hole with mud to 210'. Set rock bridge from 210' to 200' and cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

*Arthur J. Loman*  
 Conservation Division Agent