

State of Kansas



15.159.20187.0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 18 1968
 CONSERVATION DIVISION
 Wichita, Kansas

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

December 12, 1968

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Jim Davenport of Sage Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Davenport guarantees payment of the plugging fee.

Operator's full Name: Wayne E. Walcher & Petroleum, Inc.

Complete Address: 808 Central Bldg., Wichita, Kansas 67202

Lease Name: Shuler Well No. 1

Location: NE SE SE Sec. 11 Twp. 20 Rge. 9 (E)(W) X

County: Rice Total Depth 3407' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Davenport was instructed to plug the well as follows:

Fill hole with mud to 235'. Push plug and 1/4 sack hulls to 235' and cement

hole with 25 sacks cement through drill pipe. Fill hole with mud to 40'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks.

Very truly yours,

Conservation Division Agent